



DELIVERY STAGES FOR “LOG” HOUSE CONSTRUCTION SYSTEM

- A. COMPLETED OUTER SURFACES**
- B. COMPLETED OUTER SURFACES WITH ELECTRICAL INSTALLATION**
- C. COMPLETED EXTERNALLY AND INTERNALLY HOUSE**
- D. FULLY COMPLETED AND EQUIPPED HOUSE**

	A	B	C	D
Free of charge building permit. For every house above 80m ²	•	•	•	•
Construction drafts.	•	•	•	•
Check of foundation plate	•	•	•	•
External walls 120mm of glulam wood.	•	•	•	•
100mm insulation of external walls and wood lining of 15mm		•	•	•
Wooden internal wall 100 mm	•	•	•	•
50mm insulation of internal walls and wood lining of 15mm		•	•	•
Mezzanine floor	•	•	•	•
Roof	•	•	•	•
150mm roof insulation and wood lining of 15mm		•	•	•
Double PVC glazing windows and Balcony doors.	•	•	•	•
Entrance Door with aluminium external lining	•	•	•	•
Electrical installation		•	•	•
Plumbing installation		•	•	•
Screed			•	•
Sanitary equipment			•	•
Laying of bathroom and wc tiles			•	•
Floor laying			•	•
Coloring of walls			•	•
Staircase for upper floor				•
Internal doors				•
Kitchen cabinets				•
Laying of kitchen tiles				•
Wardrobes				•