

LOWENERGYHOUSES

DELIVERY STAGES FOR PASSIVE PREFAB HOUSES

A. COMPLETED OUTER SURFACES

B. COMPLETED OUTER SURFACES WITH ELECTRICAL INSTALLATIONS

C. COMPLETED EXTERNALLY AND INTERNALLY HOUSE

D. FULLY COMPLETED AND EQUIPPED HOUSE

	· ·			
	Α	В	С	D
Free of charge building permit. For every house above 80m²	•	•	•	•
Construction drafts	•	•	•	•
Check of foundation plate	•	•	•	•
External walls of 365mm with facade of expanded polystyrene or 148mm and flexible, colored, acrylic and breathable coating	•	•	•	•
200mm facade of expanded polystyrene, OSB lining and gypsum board lining of exterior walls		•	•	•
Internal walls.	•	•	•	•
100mm insulation and gypsum board lining of interior walls		•	•	•
Upper floor .	•	•	•	•
100mm insulation and gypsum board lining of ground floor roof		•	•	•
Waterproof roof.	•	•	•	•
300mm insulation and gypsum board lining of roof		•	•	•
Aluminium gutters	•	•	•	•
Triple glazing PVC windows and balcony doors	•	•	•	•
Airtight PVC entrance door	•	•	•	•
Electrical installation		•	•	•
Plumbing installation		•	•	•
Ventilation network system installation		•	•	•
Array of solar selective collectors: 8 m² with 200lt inertia tank			•	•
Screed			•	•
Air Conditioner 9000 BTU A+++			•	•
Ventilation system with energy recovery				•
Sanitary equipment			•	•
Laying of bathroom and wc tiles			•	•
Floor laying			•	•
Coloring of walls			•	•
Crown moulding			•	•
Upper floor staircase				•
Internal doors				•
Kitchen cabinets				•
Laying of kitchen tiles				•
Wardrobes				•

WEB www.easygreen.com.gr